

SAGRES CONSTRUCTION

Saint Andrews Dr NE- Westbriar to Maple

IFB 24-12 ON-CALL ROADWAY MAINTENANCE

| ITEM NO. | DESCRIPTION | ESTIMATE QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------|---|-------------------|------|------------|-------------|
| 1 | REMOVE SHRUBS | 8 | EA | \$75.00 | \$600.00 |
| 2 | REMOVE TREES (2" – 6" DIA.) | 7 | EA | \$350.00 | \$2,450.00 |
| 3 | REMOVE TREES (OVER 6" – 18" DIA.) | 4 | EA | \$1,100.00 | \$4,400.00 |
| 4 | REMOVE TREES (GREATER THAN 30" DIA.) | 1 | EA | \$5,000.00 | \$5,000.00 |
| 5 | GRIND TREE STUMP BELOW GRADE (18" DIA. AND SMALLER) | 11 | EA | \$250.00 | \$2,750.00 |
| 6 | GRIND TREE STUMP BELOW GRADE (LARGER THAN 30" DIAMETER) | 1 | EA | \$600.00 | \$600.00 |
| 7 | REMOVE AND DISPOSE OF CONCRETE DRIVEWAY APRON | 63 | SY | \$10.00 | \$630.00 |
| 8 | REMOVE AND DISPOSE OF CONCRETE SIDEWALK | 62 | SY | \$8.00 | \$496.00 |
| 9 | REMOVE AND DISPOSE OF CONCRETE CURB AND/OR CURB AND GUTTER | 264 | LF | \$8.00 | \$2,112.00 |
| 10 | REMOVE AND DISPOSE OF PAVEMENT (UP TO 4" DEPTH) | 46 | SY | \$5.00 | \$230.00 |
| 11 | REMOVE AND DISPOSE OF PAVEMENT (OVER 4" DEPTH) | 242 | SY | \$10.00 | \$2,420.00 |
| 12 | REMOVE AND RESET SIGN USING EXISTING SIGN, AND EXISTING POST | 1 | EA | \$250.00 | \$250.00 |
| 13 | INSTALL SIGN INCLUDING PROVIDING AND INSTALLING NEW 2" SQUARE BREAKAWAY POST | 3 | EA | \$250.00 | \$750.00 |
| 14 | SAWCUT ASPHALT PAVEMENT (1" – 4" DEPTH) | 523 | LF | \$1.00 | \$523.00 |
| 15 | SAWCUT CONCRETE CURB AND GUTTER, AND DRIVEWAY ENTRANCES | 35 | LF | \$1.00 | \$35.00 |
| 16 | SAWCUT CONCRETE SIDEWALK | 40 | LF | \$1.00 | \$40.00 |
| 17 | REGULAR EXCAVATION – REMOVE AND DISPOSE | 67 | CY | \$40.00 | \$2,660.00 |
| 18 | VDOT 21-A STONE OR 21-B STONE (COMPACTED IN PLACE PER VDOT STANDARDS AND SPECIFICATIONS) | 197 | TON | \$40.00 | \$7,880.00 |
| 19 | CONCRETE CURB OR CURB AND GUTTER (PER VIENNA STANDARD R-2, OR VDOT CG-2, CG-3, CG-6, OR CG-7) | 368 | LF | \$70.00 | \$25,760.00 |

IFB 24-12 ON-CALL ROADWAY MAINTENANCE

| | | | | | |
|----|--|-----|-----|------------------|---------------------|
| 20 | CONCRETE DRIVEWAY ENTRANCE, 6" THICK CONCRETE -ARL STD R-2.4C (includes 21A) | 66 | SY | \$95.00 | \$6,270.00 |
| 21 | 4" THICKNESS CONCRETE SIDEWALK | 525 | SY | \$75.00 | \$39,375.00 |
| 22 | DETECTABLE WARNING SURFACE | 70 | SF | \$45.00 | \$3,150.00 |
| 23 | ASPHALT TYPE BM-25, A THRU D | 45 | TON | \$175.00 | \$7,875.00 |
| 24 | ASPHALT TYPE SM-9.5, A THRU D | 21 | TON | \$200.00 | \$4,200.00 |
| 25 | REMOVE AND REPLACE REINFORCED CONCRETE INLET TOP (INCLUDES PROVISION OF NEW FRAME AND COVER) | 2 | SY | \$1,000.00 | \$2,200.00 |
| 26 | FURNISH AND INSTALL DRAINAGE PIPE THROUGH CURB AS SHOWN ON VIENNA DETAIL R-1, AND AS DESCRIBED IN SECTION "F" OF THIS SPECIFICATION HEREIN. | 1 | EA | \$500.00 | \$500.00 |
| 27 | RELOCATE WATER METER BOXES (HORIZONTAL AND VERTICAL RELOCATION) | 4 | EA | \$450.00 | \$1,800.00 |
| 28 | ADJUST WATER METER BOXES (VERTICAL ADJUSTMENT ONLY) | 1 | EA | \$240.00 | \$240.00 |
| 29 | REMOVE AND RELOCATE MAILBOX | 6 | EA | \$150.00 | \$900.00 |
| 30 | SODDING (TO INCLUDE 2" TOPSOIL AND FERTILIZATION) | 322 | SY | \$7.50 | \$2,415.00 |
| | | | | TOTAL BID | \$128,511.00 |