

SAGRES CONSTRUCTION Saint Bernard Drive NE

IFB 24-12 ON-CALL ROADWAY MAINTENANCE

ITEM NO.	DESCRIPTION	ESTIMATE QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	REMOVE SHRUBS	18	EA	\$75.00	\$1,350.00
2	REMOVE TREES (2" – 6" DIA.)	6	EA	\$350.00	\$2,100.00
3	REMOVE TREES (OVER 6" – 18" DIA.)	5	EA	\$1,100.00	\$5,500.00
4	GRIND TREE STUMP BELOW GRADE (18" DIA. AND SMALLER)	7	EA	\$250.00	\$1,750.00
5	GRIND TREE STUMP BELOW GRADE (OVER 18"- 30" DIA.)	1	EA	\$350.00	\$350.00
6	GRIND TREE STUMP BELOW GRADE (LARGER THAN 30" DIAMETER)	1	EA	\$600.00	\$600.00
7	REMOVE AND DISPOSE OF CONCRETE DRIVEWAY APRON	86	SY	\$10.00	\$862.50
8	REMOVE AND DISPOSE OF CONCRETE SIDEWALK	41	SY	\$8.00	\$330.24
9	REMOVE AND DISPOSE OF CONCRETE CURB AND/OR CURB AND GUTTER	270	LF	\$8.00	\$2,160.00
10	REMOVE AND DISPOSE OF PAVEMENT (UP TO 4" DEPTH)	125	SY	\$5.00	\$625.00
11	INSTALL SIGN INCLUDING PROVIDING AND INSTALLING NEW 2" SQUARE BREAKAWAY POST	1	EA	\$250.00	\$250.00
12	SAWCUT ASPHALT PAVEMENT (1" – 4" DEPTH)	435	LF	\$1.00	\$435.00
13	SAWCUT CONCRETE CURB AND GUTTER, AND DRIVEWAY ENTRANCES	85	LF	\$1.00	\$85.00
14	REGULAR EXCAVATION – REMOVE AND DISPOSE	120	CY	\$40.00	\$4,800.00
15	VDOT 21-A STONE OR 21-B STONE (COMPACTED IN PLACE PER VDOT STANDARDS AND SPECIFICATIONS)	114	TON	\$40.00	\$4,551.20
16	CONCRETE CURB OR CURB AND GUTTER (PER VIENNA STANDARD R-2, OR VDOT CG-2, CG-3, CG-6, OR CG-7)	270	LF	\$70.00	\$18,900.00
17	CONCRETE DRIVEWAY ENTRANCE, 6" THICK CONCRETE -ARL STD R-2.4C (includes 21A)	98	SY	\$95.00	\$9,310.00
18	4" THICKNESS CONCRETE SIDEWALK	360	SY	\$75.00	\$27,000.00
19	CONCRETE PAD- 4" THICK CONCRETE WITH WELDED WIRE FABRIC	48	SY	\$90.00	\$4,320.00
20	DETECTABLE WARNING SURFACE	30	SF	\$45.00	\$1,350.00

IFB 24-12 ON-CALL ROADWAY MAINTENANCE

21	ASPHALT TYPE BM-25, A THRU D	25	TON	\$175.00	\$4,375.00
22	ASPHALT TYPE SM-9.5, A THRU D	17	TON	\$200.00	\$3,308.00
23	REMOVE AND REPLACE REINFORCED CONCRETE INLET TOP (INCLUDES REMOVAL OF EXISTING FRAME AND COVER, AND RE-USE OF THE EXISTING FRAME AND COVER)	3	SY	\$950.00	\$2,850.00
24	FURNISH AND INSTALL DRAINAGE PIPE THROUGH CURB AS SHOWN ON VIENNA DETAIL R-1, AND AS DESCRIBED IN SECTION "F" OF THIS SPECIFICATION HEREIN.	1	EA	\$500.00	\$500.00
25	SEGMENTAL RETAINING WALL- MAXIMUM HEIGHT OF 4' ABOVE FINISHED GRADE, INCLUDES ONE COURSE BELOW GRADE, AND GEO-WEB NOT REQUIRED.	0	SF		\$0.00
26	RELOCATE WATER METER BOXES (HORIZONTAL AND VERTICAL RELOCATION)	4	EA	\$450.00	\$1,800.00
27	SODDING (TO INCLUDE 2" TOPSOIL AND FERTILIZATION)	255	SY	\$7.50	\$1,912.50
				TOTAL BID	\$101,374.44