

**NOTES**

1. THE PROPERTY DELINEATED ON THIS PLAT IS LOCATED ON FAIRFAX COUNTY CADASTRAL MAP No. 0384-03-0061 AND IS CURRENTLY ZONED RS-10.
2. THE PROPERTY LINES SHOWN HEREON ARE BASED ON INFORMATION OF RECORD, WITH THE RECORD BEARINGS ORIENTED TO THE VIRGINIA COORDINATE SYSTEM (VCS83), PER THE TOWN OF VIENNA REQUIREMENTS.
3. TITLE REPORT FURNISHED BY TYSONS TITLE AGENCY, LLC, FILE NO. TT-VA-944, DATE JULY 30, 2024.
4. THE PLAT OF THE PROPERTY SHOWN HEREON IS REFERENCED TO THE VIRGINIA COORDINATE SYSTEM (VCS83), NORTH ZONE, US SURVEY FOOT UNITS AS COMPUTED FROM A FIELD SURVEY WHICH TIES THIS BOUNDARY TO NATIONAL GEODETIC SURVEY (NGS) PID HV8501, DESIGNATION JADES.  
  
THE COMBINED GRID AND ELEVATION FACTOR IS 0.99994138409712.
5. THE PROPERTY SHOWN HEREON LIES WITHIN ZONE 'X', AN AREA DETERMINED TO BE OUTSIDE THE 0.2% ANNUAL CHANCE FLOODPLAIN, AS DELINEATED ON FLOOD INSURANCE RATE MAP NO. 51059C0145E, PANEL 145 OF 450, WITH AN EFFECTIVE DATE OF SEPTEMBER 17, 2010.
6. THERE ARE NO RESOURCE PROTECTION AND RESOURCE MANAGEMENT AREAS ON THIS SITE, AS SHOWN ON THE TOWN OF VIENNA CHESAPEAKE BAY PRESERVATION AREAS MAP, PREPARED ON NOVEMBER 21, 2005.
7. THE PERIMETER OF THE LAND HEREON PLATTED WILL BE MONUMENTED USING IRON PIPE OR OTHER PERMANENT MARKERS. MONUMENTATION OF INTERNAL LOTS, STREETS, OUTLOTS, AND PARCELS CREATED BY RECORDATION OF THIS PLAT ARE COVERED BY SUBDIVISION ORDINANCE AND SURVEY BOND AND WILL BE INSTALLED BY A LAND SURVEYOR LICENSED IN THE COMMONWEALTH PRIOR TO BOND RELEASE BY THE TOWN OF VIENNA.

**SURVEYOR'S CERTIFICATE**

I, KEVIN D. VAUGHN, A DULY LICENSED LAND SURVEYOR IN THE COMMONWEALTH OF VIRGINIA, DO HEREBY CERTIFY THAT THIS PLAT IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF; THAT IT IS THE PROPERTY OF THE ESTATE OF ROBERT L. THOMPSON, JR., RECORDED AT WILL BOOK 01322 AT PAGE 1103, AMONG THE LAND RECORDS OF FAIRFAX COUNTY, VIRGINIA.


I FURTHER CERTIFY THAT THE PROPERTY LIES WITHIN THE BOUNDS OF THE ORIGINAL TRACT AND THAT THE BEARINGS REFER TO EXISTING LAND RECORDS (LIBER J-9 FOLIO 460).



**OWNER'S CONSENT AND DEDICATION**

THE PLATTING OR DEDICATION OF THE FOLLOWING DESCRIBED LAND, LOT 61A, WILMAR PLACE, IS WITH THE FREE CONSENT AND IN ACCORDANCE WITH THE DESIRE OF THE UNDERSIGNED OWNER(S), PROPRIETOR(S), AND TRUSTEE(S), IF ANY.

BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 ESTATE OF ROBERT L. THOMPSON, JR.  
 BY: REGINA SALTA  
 (REGINA SALTA IS AUTHORIZED SIGNATORY OF THE ESTATE OF ROBERT L. THOMPSON, JR.)



**VICINITY MAP**  
SCALE: 1" = 2000

**AREA TABULATION**

LOT 61	3,500 S.F. OR 0.08035 ACRES
LOT 62	3,500 S.F. OR 0.08035 ACRES
LOT 61A	7,000 S.F. OR 0.16070 ACRES

**SITE ANALYSIS**


DESCRIPTION	REQUIRED/ALLOWED	PROVIDED/EXISTING
ZONE	RS-10	RS-10
LOT AREA	10,000 SF	7,000 SF
LOT WIDTH	45/60/75	50.0/50.0/50.0

**SHAPE FACTOR CALCULATION**

LOT NUMBER	LOT PERIMETER	LOT AREA	LOT SHAPE FACTOR
61A	380.00'	7,000	20.63

PER THE TOWN OF VIENNA ZONING ORDINANCE, THE MATHEMATICAL FORMULA FOR DETERMINING THE SHAPE FACTOR IS  $(P)^2/A$ , WHERE P EQUALS PERIMETER AND A EQUALS THE AREA OF THE LOT.

<b>TOWN OF VIENNA</b>
TOWN MAYOR
TOWN CLERK



PRELIMINARY PLAT SHOWING THE VACATION AND CONSOLIDATION OF LOTS 61 AND 62

**WILMAR PLACE**  
DEED BOOK J-9 PAGE 461  
TOWN OF VIENNA  
HUNTER MILL DISTRICT  
FAIRFAX COUNTY, VIRGINIA


SCALE:  
N/A

SHEET 1 OF 2

DATE:  
AUGUST 13, 2024

DRAFT: TJC      CHECK: KDV


FILE NUMBER  
24091-1-0 140



N/F  
**MANUEL B. FESDEKJIAN**  
**MARIA H. FESDEKJIAN**  
(D.B. 7769 PG. 1771)  
CADASTRAL MAP #0384-02-0099  
ZONE : C-1B USE : CONVERTED RESIDENTIAL OFFICE (EX. DWELLING)


N/F  
**MARYAM PROPERTIES, LLC**  
(D.B. 19669 PG. 847)  
CADASTRAL MAP #0384-02-0098  
ZONE : C-1B USE : APPAREL & ACCESSORIES

**15' ALLEY**  
(UNIMPROVED)  
S43°38'58"W 50.00'



PRELIMINARY PLAT SHOWING THE VACATION AND CONSOLIDATION OF  
LOTS 61 AND 62

**WILMAR PLACE**  
DEED BOOK J-9 PAGE 461  
TOWN OF VIENNA  
HUNTER MILL DISTRICT  
FAIRFAX COUNTY, VIRGINIA



SCALE:  
1" = 20'

SHEET 2 OF 2

DATE:  
AUGUST 13, 2024

DRAFT: TJC      CHECK: KDV

FILE NUMBER  
24091-1-0 140