

D/F MONUMENT SIGN -REFACE

1" = 1'-0"



DESCRIPTION OF WORK:

FURNISH AND INSTALL (1) ONE REPLACEMENT FACE IN EXISTING 1'-8" X 8' D/F MONUMENT SIGN CABINET.

FACE OF 3/16" WHITE #7328 PLEXIGLAS OVERLAID WITH DURONAUTIC OPAQUE BRONZE VINYL.
COPY TO BE WHITE, LOGO TO BE WHITE, GREEN TO MATCH 3630-76 HOLLY GREEN AND GOLD YELLOW TO MATCH 3630-125.

EXTERIOR OF CABINET & RETAINERS TO BE PAINTED SW#7675 SEALSKIN WHILE ONSITE DOING REFACE WORK.

LAMPS, BALLAST AND ANY REQUIRED SOCKETS/WIRING TO BE REPLACED AS NEEDED SO SIGN LIGHTS 100%.



EXISTING



PROPOSED

Town of Vienna
Approved
09/03/2021

Board of Architecture Review
APPROVED
August 19, 2021

SIDE WALL SIGN -REFACE

1" = 1'-0"



DESCRIPTION OF WORK:

FURNISH AND INSTALL (1) ONE REPLACEMENT FACE IN EXISTING 3' X 8' S/F WALL SIGN CABINET

FACE OF 3/16" WHITE #7328 PLEXIGLAS OVERLAID WITH DURONAUTIC OPAQUE BRONZE VINYL.
COPY TO BE WHITE, LOGO TO BE WHITE, GREEN TO MATCH 3630-76 HOLLY GREEN AND GOLD YELLOW TO MATCH 3630-125.

EXTERIOR OF CABINET & RETAINERS TO BE PAINTED SW#7675 SEALSKIN WHILE ONSITE DOING REFACE WORK.

LAMPS, BALLAST AND ANY REQUIRED SOCKETS/WIRING TO BE REPLACED AS NEEDED SO SIGN LIGHTS 100%.



EXISTING



PROPOSED

Town of Vienna
Approved
09/03/2021

Board of Architecture Review
APPROVED
August 19, 2021

FRONT WALL SIGN -REFACE

1" = 1'-0"



DESCRIPTION OF WORK:

FURNISH AND INSTALL (1) ONE REPLACEMENT FACE IN EXISTING 3' X 8' S/F WALL SIGN CABINET

FACE OF 3/16" WHITE #7328 PLEXIGLAS OVERLAID WITH DURONAUTIC OPAQUE BRONZE VINYL.
COPY TO BE WHITE, LOGO TO BE WHITE, GREEN TO MATCH 3630-76 HOLLY GREEN AND GOLD YELLOW TO MATCH 3630-125.

EXTERIOR OF CABINET & RETAINERS TO BE PAINTED SW#7675 SEALSKIN WHILE ONSITE DOING REFACE WORK.

LAMPS, BALLAST AND ANY REQUIRED SOCKETS/WIRING TO BE REPLACED AS NEEDED SO SIGN LIGHTS 100%.



EXISTING



PROPOSED

Town of Vienna
Approved
09/03/2021

Board of Architecture Review
APPROVED
August 19, 2021