

WATERSHED: DIFFICULT RUN

COMMENCING WORK AND FOR ANY DAMAGES WHICH OCCUR BY HIS FAILURE TO LOCATE OR PRESERVE THESE UNDERGROUND AND OVERHEAD UTILITIES. IF, DURING CONSTRUCTION OPERATIONS, THE CONTRACTOR ENCOUNTERS UTILITIES OTHER THAN THOSE INDICATED BY MISS UTILITIES AND MEMBER UTILITY COMPANIES, HE (SHE) SHALL IMMEDIATELY NOTIFY THE OWNER AND TAKÈ NECESSARY AND APPROPRIATE STEPS TO PROTECT THE FACILITY AND ASSURE THE CONTINUANCE OF SERVICE. THE CONTRACTOR IS REQUIRED BY LAW TO NOTIFY MISS UTILITY @ 1-800-552-7001 AT LEAST 48 HOURS IN ADVANCE OF THE START OF ANY WORK ON THIS PROJECT.

. THE SITE CONTRACTOR /DEVELOPER MUST VERIFY THE LOCATIONS AND ELEVATIONS OF ALL PUBLIC AND PRIVATE UTILITIES AND STRUCTURES AFFECTING THE SITE PRIOR TO THE START OF THE CONSTRUCTIONS. ANY CONFLICT WITH THE PLAN MUST BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY FOR RESOLUTION. FAILURE TO VERIFY EXISTING UTILITIES MAY RESULT IN COSTLY DELAYS IN REMEDIAL MEASURES.

TOWN OF VIENNA GENERAL NOTES:

1. A PRE-CONSTRUCTION MEETING MUST BE HELD PRIOR TO THE START OF CONSTRUCTION. CALL 703-255-6384 SCHEDULE PRE-CONSTRUCTION MEETING.

2. ALL CONSTRUCTION GENERATED DEBRIS MUST BE HAULED AWAY BY THE CONTRACTOR OR OWNER. 3. PRIOR TO THE REMOVAL OF ANY TOWN TREES (TREES WITHIN THE RIGHT OF WAY), THE APPLICANT ÒR THEIR REPRESENTATIVE SHALL CONTACT THE TOWN OF VIENNA ARBORIST AT 703-255-6360 TO COORDINATE HAVING THE TOWN ARBORIST ONSITE DURING ALL TOWN TREE REMOVAL

4. TREE PROTECTION FOR ANY TOWN TREE, AS SHOWN ON PLAN, MUST BE INSTALLED PRIOR TO ANY SITE WORK. 5. IT IS UNLAWFUL TO PERFORM ANY CONSTRUCTION

FOUNDATION CORNERS PRIOR TO APPROVAL OF SETBACKS. WORK COMPLETED IN VIOLATION OF THIS REQUIREMENT IS SUBJECT TO DEMOLITION.

5. ALL DUMPSTERS/PODS ARE TO BE PLACED ON PRIVATE PROPERTY. 1. FRONT ELEVATION CHECKS ARE REQUIRED. WALL CHECK SURVEYS ARE REQUIRED AND MUST

E SUBMITTED PRIOR TO CONSTRUCTION ABOVE FOUNDATION CORNERS. 9. A CERTIFICATE OF OCCUPANCY IS REQUIRED PRIOR O OCCUPANCY. ALL REQUIRED DOCUMENTATION AND INSPECTIONS MUST BE SUBMITTED/COMPLETED BEFORE THE TOWN OF VIENNA WILL ISSUE A

CERTIFICATE OF OCCUPANCY. 10. EXISTING SANITARY SEWER LATERALS ARE TYPICALLY CAPPED AT OR NEAR THE PROPERTY LINE. THE REUSE OF THE PORTION OF THE EXISTING SANITARY SEWER LATERAL BETWEEN THE TOWN OWNED SEWER MAIN AND THE CAPPED END MAY BE ALLOWED PROVIDING THAT A LICENSED PLUMBER CERTIFIES THAT THE EXISTING PIECE OF PIPE IS GRADED PROPERLY AND IN LIKE NEW CONDITION. THE REUSE OF A PORTION OF THE EXISTING LATERAL DOES NOT IMPLY THAT THE TOWN IS WARRANTING

THE CONDITION IN ANY WAY. CONSTRUCTION ENTRANCE NOTE:

DEPENDING ON ACTUAL SITE CONDITIONS AND LIMITATIONS, IN THE FIELD THE SITE INSPECTOR MAY ALLOW AN EXISTING DRIVEWAY TO BE USED AS A CONSTRUCTION ENTRANCE, OR THE LENGTH OF THE STANDARD CONSTRUCTION ENTRANCE TO BE MODIFIED. IF THE CONSTRUCTION ENTRANCE LENGTH IS TO BE INSTALLED AND IS LESS THAN 70 FEET (MINIMUM REQUIRED), A WASH RACK MAY BE REQUIRED TO WASH VEHICLE WHEELS BEFORE ENTERING THE STREET.


INSTALL GRAVEL CONSTRUCTION ENTRANCE AS DEEMED NECESSARY PER INSTRUCTION OF SITE INSPECTOR.


2. THE CONTRACTOR/OWNER SHALL PROVIDE SEPARATE WATER TANK/WATER HOSE TO WASH THE VEHICLE WHEELS.

3. STREET SWEEPING IS REQUIRED EVERYTIME THE SEDIMENT IS TRANSPORTED TO THE PUBLIC STREET, AND THE PUBLIC STREET SHALL REMAIN SEDIMENT FREE AT ALL THE TIME OF THE CONSTRUCTION

SHEET 9 TREE PRESERVATION NOTES & DETAILS

		01
	INDEX	
	SHEET	DESCRIPTION
	SHEET 1	INFILL LOT PLAN, EXISTING CONDITIONS PLAN, DEMOLITION, E&S CONTROL PLAN-PHASE I
	SHEET 2	SITE GRADING PLAN, E&S CONTROL PLAN-PHASE II
	SHEET 3	BUILDING HEIGHT COMPUTATIONS, GENERAL NOTES AND 1" WATER METER DETAIL
	SHEET 3A	PRE AND POST DEVELOPMENT MAPS AND COMPUTATIONS
ı	SHEET 3B	HYDROGRAPHS
	SHEET 4	STORMWATER COMPUTATIONS AND LOT DEVIATION TABLE
	SHEET 5	RUNOFF REDUCTION SPREADSHEETS, INFILTRATION TEST
	SHEET 5A	PRE AND POST DEVELOPMENT RUNOFF
	SHEET 6	BMP DESIGN AND SUB-DRAINAGE MAP FACILITY #1
	SHEET 6A	BMP DESIGN AND SUB-DRAINAGE MAP FACILITY #2
ı	SHEET 6B	BMP NOTES AND DETAILS
ı	SHEET 6C	INFILTRATION SOIL REPORT FACILITY #1
ı	SHEET 6D	INFILTRATION SOIL REPORT FACILITY #2
	SHEET 7	TREE PRESERVATION NOTES & DETAILS
	SHEET 8	EXISTING TREE INVENTORY AND TREE CONSERVATION PLAN





SCALE: 1": 300'

THE SOIL FROM EXCAVATING FOUNDATION WILL BE STOCKPILED IN THE AREA AS SHOWN ON THIS SITE PLAN. DURING CONSTRUCTION OF THE PROJECT, SOIL STOCKPILES AND BORROW AREAS SHALL BE STABILIZED OR PROTECTED WITH SEDIMENT TRAPPING MEASURES. ALL SOIL STOCKPILES, IF ANY, SHALL BE SEEDED AND MULCHED WITHIN 7 DAYS AFTER GRADING. THE HEIGHT OF THE STOCKPILES MATERIAL SHALL NOT EXCEED 4 FT. THE MAXIMUM SLOPE OF THE STOCKPILE MATERIAL SHALL NOT BE MORE THAN 3:1.

THE STOCKPILE MATERIAL SHALL BE PROTECTED FROM DRAINING INTO ADJOINING NON DISTURBED AREA BY SUPER SILT FENCE OR ANY OTHER SEDIMENT CONTROL DEVICES. THE STOCKPILE MATERIAL SHALL BE HAULED AWAY FROM THE SITE DAY TO DAY AS FAR AS POSSIBLE. THE EXCESS OR UNUSED STOCKPILE MATERIALS SHALL BE REMOVED FROM THE SITE AND WILL BE DUMPED AT APPROVED DUMPING SITE.

THE GRADING/ EXCAVATION CONTRACTOR FOR THE SUBJECT SITE IS REQUIRED TO NOTIFY, IN WRITING, THE ASSIGNED SITE INSPECTOR REGARDING ANY EXCESS MATERIAL PROPOSED TO BE HAULED OFFSITE PRIOR TO HAULING. THE NOTIFICATION MUST INDICATE THE QUANTITY OF MATERIAL TO BE MOVED OFFSITE, IDENTIFICATION OF THE RECEIVING SITE WHERE THE EXCESS WILL BE TAKEN, ALL INFORMATION NECESSARY TO SHOW THAT SUCH RECEIVING SITE HAS BEEN PROPERLY PERMITTED AND HAS E&S CONTROLS INSTALLED.

(VA E&S SEDIMENT CONTROL HANDBOOK, PAGE VI-13 MINIMUM STANDARDS, OFFSITE AREAS AND TABLE 6-1, PG VI 15, ES-5)

WETLANDS CERTIFICATE

I HEREBY CERTIFY THAT ALL WETLANDS PERMITS REQUIRED BY LAW WILL BE OBTAINED PRIOR

TO COMMENCING LAND DISTURBANCE ACTIVITIES. 04/15/2024 PARKS MICHAEL OWNER NAME: SIGNATURE:

LEGALITY OF LOT CERTIFICATION

HEREBY CERTIFY THAT ALL APPROPRIATE COUNTY APPROVALS WERE OBTAINED IN ACCORDANCE WITH THE PROCESS REQUIRED BY THE SUBDIVISION ORDINANCE IN EFFECT AT THE TIME OF THE CREATION. THE LOT WAS CREATED AS PART OF WINDOVER HEIGHTS, BLK 4, AS APPROVED BY FAIRFAX COUNTY AND RECORDED IN DEED BOOK 122 PAGE 83B AMONG THE LAND RECORDS OF FAIRFAX COUN?



DATE: **04/15/2024**

PHASE I EROSION AND SEDIMENT CONTROL PROGRAM:


1. DEPENDING ON ACTUAL SITE CONDITIONS AND LIMITATIONS, IN THE FIELD THE SITE INSPECTOR MAY ALLOW AN EXISTING DRIVEWAY TO BE USED AS A CONSTRUCTION


SIGNATURE

ENTRANCE, OR THE LENGTH OF THE STANDARD CONSTRUCTION ENTRANCE TO BE MODIFIED. 2. INSTALL SILT FENCE AND ROOT PRUNING TRENCH AS SHOWN ON THIS PLANS. 3. CONTACT THE TOWN INSPECTOR FOR APPROVAL OF THE INSTALLED PERIMETER CONTROL

MEASURES PRIOR TO FURTHER LAND-DISTURBING ACTIVITIES. 4. ROUGH GRADE THE REMAINDER OF THE SITE WITHIN THE LIMIT OF DISTURBANCE.

5. PERFORM STABILIZATION SUCH AS TEMPORARY SEEDING AND MULCHING FOR ALL AFFECTED AREAS.





Dgu 0 **(**

Φ

(

					DAT	
REVISION BLOCK					NO. DESCRIPTION	
					Z	
SEAL	RGI	NI	A	H.	IN,	

4 / 8 %

HEIGH OVER , TOWN

FAX MAP: 038 - 3 - ((02)) - 007OCT 2023 PREP. BY: | A.V CHECKED BY: D.C PROJECT # |2023-8071-011 SCALE: 1"= 20' \mathbf{OF} SHEET: 1