

IFB 24-12 ON-CALL ROADWAY MAINTENANCE - SAGRES CONSTRUCTION CORPORATION

KINGSLEY RD SE-

8/17/2024

BID ITEM NO.	DESCRIPTION	ESTIMATE QUANTITY	UNIT	SAGRES UNIT PRICE	AMOUNT
2	REMOVE SHRUBS	14	EA	\$75.00	\$1,050.00
3	REMOVE TREES (2" – 6" DIA.)	24	EA	\$350.00	\$8,400.00
4	REMOVE TREES (OVER 6" – 18" DIA.)	2	EA	\$1,100.00	\$2,200.00
7	GRIND TREE STUMP BELOW GRADE (18" DIA. AND SMALLER)	26	EA	\$250.00	\$6,500.00
12	REMOVE AND DISPOSE OF CONCRETE DRIVEWAY APRON	96	SY	\$10.00	\$960.00
13	REMOVE AND DISPOSE OF CONCRETE SIDEWALK	165	SY	\$8.00	\$1,320.00
14	REMOVE AND DISPOSE OF CONCRETE CURB AND/OR CURB AND GUTTER	1034	LF	\$8.00	\$8,272.00
15	REMOVE AND DISPOSE OF PAVEMENT (UP TO 4" DEPTH)	86	SY	\$5.00	\$430.00
16	REMOVE AND DISPOSE OF PAVEMENT (OVER 4" DEPTH)	1121	SY	\$10.00	\$11,210.00
17	REMOVE AND DISPOSE OF BRICK AND OR/CONCRETE PAVERS	15	SY	\$10.00	\$150.00
20	ERADICATE PAVEMENT MARKINGS (LINEAR MARKINGS) PER VDOT SECTION 512	150	LF	\$20.00	\$3,000.00
25	FURNISH AND INSTALL INLET PROTECTION (GUTTER BUDDY OR EQUIVALENT)	3	EA	\$190.00	\$570.00
28	SAWCUT ASPHALT PAVEMENT (1" – 4" DEPTH)	1231	LF	\$1.00	\$1,231.00
29	SAWCUT CONCRETE CURB AND GUTTER, AND DRIVEWAY ENTRANCES	73	LF	\$1.00	\$73.00
31	REGULAR EXCAVATION – REMOVE AND DISPOSE	289	CY	\$40.00	\$11,560.00
34	VDOT 21-A STONE OR 21-B STONE (COMPACTED IN PLACE PER VDOT STANDARDS AND SPECIFICATIONS)	384	TON	\$40.00	\$15,360.00
41	CONCRETE CURB OR CURB AND GUTTER (PER VIENNA STANDARD R-2, OR VDOT CG-2, CG-3, CG-6, OR CG-7)	1035	LF	\$70.00	\$72,450.00
42	CONCRETE DRIVEWAY ENTRANCE, 7" THICK CONCRETE -VDOT CG-9B AND CG-9D (includes 21A)	142	SY	\$95.00	\$13,490.00
43	CONCRETE DRIVEWAY ENTRANCE, 6" THICK CONCRETE -ARL STD R-2.4C (includes 21A)	12	SY	\$95.00	\$1,140.00

IFB 24-12 ON-CALL ROADWAY MAINTENANCE - SAGRES CONSTRUCTION CORPORATION

45	4" THICKNESS CONCRETE SIDEWALK	655	SY	\$75.00	\$49,125.00
49	DETECTABLE WARNING SURFACE	20	SF	\$45.00	\$900.00
51	FURNISH AND INSTALL BRICK SIDEWALK PAVERS (2-3/8" THICKNESS) INCLUDES 4" THICK CONCRETE BASE (A-3), AND MORTAR SETTING BED	23	SY	\$210.00	\$4,830.00
52	CONCRETE STEPS (WIDTH 3' to 5')	1	EA	\$200.00	\$200.00
53	ASPHALT TYPE BM-25, A THRU D	156	TON	\$175.00	\$27,300.00
54	ASPHALT TYPE SM-9.5, A THRU D	61	TON	\$200.00	\$12,200.00
60	REMOVE EXISTING MANHOLE STRUCTURE	1	EA	\$1,200.00	\$1,200.00
73	FURNISH AND INSTALL CURB DROP INLET, VDOT DI-3B, OR DI-3C WITH L = 8' (DEPTH 5' OR LESS)	1	EA	\$11,500.00	\$11,500.00
114	FURNISH AND INSTALL VDOT STANDARD UD-4 EDGE DRAIN from sta 16+00 to inlet at Desale	535	LF	\$35.00	\$18,725.00
115	TIE-IN TO EXISTING STRUCTURE (12" - 18" STORM SEWER PIPE)	1	EA	\$2,000.00	\$2,000.00
123	REMOVE AND REPLACE REINFORCED CONCRETE INLET TOP (INCLUDES PROVISION OF NEW FRAME AND COVER)	1	SY	\$1,000.00	\$1,000.00
133	STONE RETAINING WALL (ARL STD R-4.0, R-4.1, R4.2 AND AS DESCRIBED IN SECTION "F" OF THIS SPECIFICATION HEREIN)	40	CF	\$35.00	\$1,400.00
138	ADJUST WATER METER BOXES (VERTICAL ADJUSTMENT ONLY)	7	EA	\$240.00	\$1,680.00
139	REMOVE AND RELOCATE MAILBOX	11	EA	\$150.00	\$1,650.00
141	GAS VALVE- VERTICAL ADJUSTMENT TO NEW GRADE	5	EA	\$450.00	\$2,250.00
143	CONCRETE TESTING SERIES (AS DESCRIBED IN SECTION "F" OF THE SPECIFICATION HEREIN)	4	EA	\$500.00	\$2,000.00
145	SODDING (TO INCLUDE 2" TOPSOIL AND FERTILIZATION)	1041	SY	\$7.50	\$7,807.50
147	FILL DIRT	388	CY	\$25.00	\$9,700.00
NIC	REMOVE AND RESET LAMP POST	2	EA	\$500.00	\$1,000.00
				TOTAL BID	\$315,833.50