POLE FOUNDATION SCHEDULE

POLE DESIGNATION	FORCES (1.)			DRILLED PIER		
	MOMENT (M) FT-LBS	SHEAR (V) LBS	VERTICAL (P) LBS	DIAMETER INCHES	EMBEDMENT DEPTH	CONCRETE BACKFILL YD ³ (2.)
T1 - T4	10,391	432	464	30	8'-0"	1.0

- ASD LOAD COMBINATION D + 0.6W. VERTICAL FORCE IS WEIGHT OF DRESSED POLE (DOES NOT INCLUDE PRECAST BASE WEIGHT).
- 2. MINIMUM CONCRETE BACKFILL VOLUME, SITE CONDITIONS MAY REQUIRE ADDITIONAL BACKFILL.

PRECAST BASE IDENTIFICATION							
PRECAST BASE TYPE	PRECAST BASE WEIGHT	PRECAST BASE LENGTH	PROJECTION ABOVE GRADE		OUTSIDE DIAMETER		
1B	920 LBS	15'-2"	7'-2"	8'-0"	9.56"		

POLE IDENTIFICATION						
POLE DESIGNATION	POLE TYPE	PRECAST BASE TYPE	FIXTURE CONFIGURATION (FIX. PER XARM)	FIXTURE AND ACCESSORIES EPA (FT ²)		
T1 - T4	LSS40A	1B	2 (2)	2.5		

DESIGN NOTES

Attachment 04

DESIGN PARAMETERS:

 $\overline{\text{WIND V}} = 115 \text{ MPH, V}_{\text{asd}} = 89 \text{ MPH (EXPOSURE C, RISK CATEGORY II) PER}$ VIRGINIA CONSTRUCTION CODE, 2021 EDITION (IBC 2021 / ASCE 7-22). DESIGN WIND PARAMETERS ARE AS NOTED, ACTUAL EXPOSURE MUST BE VERIFIED FOR THE SITE BY THE PROPER GOVERNING OFFICIAL.

GEOTECHNICAL PARAMETERS:

ALLOWABLE END BEARING SOIL PRESSURE: 1,500 PSF OR SKIN FRICTION: 250 PSF ALLOWABLE LATERAL SOIL BEARING PRESSURE: 200 PSF/FT (NEGLECT TO -2'-0") IN ACCORDANCE WITH THE 2021 EDITION OF THE VIRGINIA CONSTRUCTION CODE. CHAPTER 18. SEE TABLE 1806.2, SOIL MATERIAL CLASS 5 & SECTION 1806.3.4.

DESIGN SOIL PARAMETERS ARE AS NOTED. ACTUAL ALLOWABLE SOIL PARAMETERS MUST BE VERIFIED ON SITE.

A GEOTECHNICAL ENGINEER OR REPRESENTATIVE OF IS RECOMMENDED (NOT REQUIRED) TO BE AVAILABLE AT THE TIME OF THE FOUNDATION INSTALLATION TO VERIFY THE SOIL DESIGN PARAMETERS AND TO PROVIDE ASSISTANCE IF ANY PROBLEMS ARISE IN FOUNDATION INSTALLATION.

ENCOUNTERING SOIL FORMATIONS THAT WILL REQUIRE SPECIAL DESIGN CONSIDERATIONS OR EXCAVATION PROCEDURES MAY OCCUR. POLE FOUNDATIONS WILL NEED TO BE ANALYZED ACCORDING TO THE SOIL CONDITIONS THAT EXIST. IF ANY DISCREPANCIES OR INCONSISTENCIES ARISE, NOTIFY THE ENGINEER OF SUCH DISCREPANCIES. FOUNDATIONS WILL THEN BE REVISED ACCORDINGLY. REVISIONS WILL BE ANALYZED PER RECOMMENDATIONS DIRECTED BY A REGISTERED ENGINEER.

ALL EXCAVATIONS MUST BE FREE OF LOOSE SOIL AND DEBRIS PRIOR TO FOUNDATION INSTALLATION AND CONCRETE BACKFILL PLACEMENT. TEMPORARY CASINGS OR DRILLERS SLURRY MAY BE USED TO STABILIZE THE EXCAVATION DURING INSTALLATION. CASINGS MUST BE REMOVED DURING CONCRETE BACKFILL PLACEMENT CONCRETE BACKFILL MUST BE PLACED WITH A TREMIE WHEN SLURRY OR WATER IS PRESENT WITHIN THE EXCAVATION.

CONTRACTOR MUST BE FAMILIAR WITH THE COMPLETE SOIL INVESTIGATION REPORT AND BORINGS, AND CONTACT THE GEOTECHNICAL FIRM (IF NECESSARY) TO UNDERSTAND THE SOIL CONDITIONS AND THE POSSIBILITY OF GROUND WATER PUMPING AND EXCAVATION STABILIZATION OR BRACING DURING PRECAST BASE INSTALLATION AND PLACEMENT OF CONCRETE BACKFILL.

CONCRETE SHALL BE AIR-ENTRAINED AND HAVE A MINIMUM COMPRESSIVE DESIGN STRENGTH AT 28 DAYS OF 3,000 PSI. 3,000 PSI CONCRETE SPECIFIED FOR EARLY POLE ERECTION, ACTUAL REQUIRED MINIMUM ALLOWABLE CONCRETE STRENGTH IS 1,000 PSI. ALL PIERS AND CONCRETE BACKFILL MUST BEAR ON AND AGAINST FIRM UNDISTURBED SOIL.

GENERAL NOTES:

FIXTURES MUST BE LOCATED TO MAINTAIN 10'-0" MINIMUM HORIZONTAL CLEARANCE FROM ANY OBSTRUCTION. ENGINEER MUST BE NOTIFIED IF FOUNDATIONS ARE NEAR ANY RETAINING WALLS OR WITHIN / NEAR ANY SLOPES STEEPER THAN 3H: 1V. POLES, FIXTURES, PRECAST BASES, ELECTRICAL ITEMS AND INSTALLATION PER MUSCO LIGHTING.

> KYLE G. LACINA Lic. No. 039348

CUNNINGHAM **OURT LIGHTING TENNIS FCPA**

VIENNA,

PARK



 \circ 114 NICHOLAS DRIVE MARSHALLTOWN, IOWA 50158 PHONE NUMBER: 641-752-6334 EMAIL: MSL.INFO@SEPC.BIZ Δ. STRUCTURAL ENGINEERS, I NGINEERS,

ROJECT NUMBER

241496

DATE 25 AUGUST 2025

OF ONE

DRAWING NUMBER

C1

POLE FOUNDATION ELEV.

SCALE: NOT TO SCALE

LIGHT STRUCTURE~

STEEL POLE BY

(SEE POLE ID)

DRILLED PIER EMBEDMENT DEPTH SEE POLE FOUNDATION SCHEDULE)

MUSCO LIGHTING

SOIL BACKFILL NOTE:

THE TOP TWO FEET OF ANNULUS SHALL BE BACKFILLED WITH SOIL, WITH A CLASSIFICATION OF CLASS 5 (TABLE 1806.2) OR BETTER. COMPACTION, 95% FOR COHESIVE SOIL AND 98% FOR A COHESIONLESS SOIL BASED UPON STANDARD PROCTOR TESTING (ASTM D698).

SOIL BACKFILL

SEE NOTE BELOW

LIGHT STRUCTURE

PRECAST BASE BY MUSCO LIGHTING (SEE POLE ID)

CONCRETE

BACKFILL

UNDISTURBED,

IN-SITU SOIL ~

DRILLED PIER DIAMETER (SEE POLE FNDTN, SCH.)