

SPECIAL INSPECTIONS AND TESTS (IBC 2018)

1. THE PRIME CONTRACTOR SHALL EMPLOY ONE OR MORE APPROVED AGENCIES TO PROVIDE SPECIAL INSPECTIONS AND TESTS DURING CONSTRUCTION ON THE TYPES OF WORK SPECIFIED BELOW AND IDENTIFY THE APPROVED AGENCIES TO THE BUILDING OFFICIAL.
2. THE APPROVED AGENCIES SHALL PROVIDE WRITTEN DOCUMENTATION TO THE BUILDING OFFICIAL DEMONSTRATING THE COMPETENCE AND RELEVANT EXPERIENCE OR TRAINING OF THE SPECIAL INSPECTORS WHO WILL PERFORM THE SPECIAL INSPECTIONS AND TESTS DURING CONSTRUCTION.
3. THE CONSTRUCTION OR WORK FOR WHICH SPECIAL INSPECTION OR TESTING IS REQUIRED SHALL REMAIN ACCESSIBLE AND EXPOSED FOR SPECIAL INSPECTION OR TESTING PURPOSES UNTIL COMPLETION OF THE REQUIRED SPECIAL INSPECTIONS OR TESTS.
4. APPROVED AGENCIES SHALL KEEP RECORDS OF SPECIAL INSPECTIONS AND TESTS. THE APPROVED AGENCY SHALL SUBMIT REPORTS OF SPECIAL INSPECTIONS AND TESTS TO THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE. REPORTS SHALL INDICATE THAT WORK INSPECTED OR TESTED WAS OR WAS NOT COMPLETED IN CONFORMANCE TO APPROVED CONSTRUCTION DOCUMENTS. DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION. IF THEY ARE NOT CORRECTED, THE DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE BUILDING OFFICIAL AND TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE PRIOR TO THE COMPLETION OF THAT PHASE OF WORK. A FINAL REPORT DOCUMENTING REQUIRED SPECIAL INSTRUCTIONS AND TESTS, AND CORRECTION OF ANY DISCREPANCIES NOTED IN THE INSPECTIONS OR TESTS, SHALL BE SUBMITTED AT A POINT IN TIME AGREED UPON PRIOR TO THE START OF WORK BY THE OWNER OR THE OWNER'S AUTHORIZED AGENT TO THE BUILDING OFFICIAL.
5. REFER TO 2018 INTERNATIONAL BUILDING CODE FOR DEFINITION OF TERMS.

SOILS CONSTRUCTION (IBC 1705.6)

1. VERIFY SUBGRADE IS ADEQUATE TO ACHIEVE DESIGN BEARING CAPACITY	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	PRIOR TO PLACEMENT OF CONCRETE
2. VERIFY EXCAVATIONS EXTEND TO PROPER DEPTH AND MATERIAL	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	PRIOR TO PLACEMENT OF COMPACTED FILL OR CONCRETE.
3. VERIFY THAT SUBGRADE HAS BEEN APPROPRIATELY PREPARED PRIOR TO PLACING COMPACTED FILL	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	PRIOR TO PLACEMENT OF COMPACTED FILL
4. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	ALL MATERIALS SHALL BE CHECKED AT EACH LIFT FOR PROPER CLASSIFICATIONS AND GRADATIONS NOT LESS THAN ONCE FOR EACH 10,000FT ² OF SURFACE AREA.
5. VERIFY PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION.	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	

CONCRETE CONSTRUCTION (IBC 1705.3 AND IBC CHAPTER 19)

1. REINFORCING STEEL, INCLUDING PRESTRESSING TENDONS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY PRIOR TO PLACING CONCRETE THAT REINFORCING IS OF SPECIFIED TYPE, GRADE AND SIZE; THAT IT IS FREE OF OIL, DIRT AND RUST; THAT IT IS LOCATED AND SPACED PROPERLY; THAT HOOKS, BENDS, TIES, STRIPPERS AND SUPPLEMENTAL REINFORCEMENT ARE PLACED CORRECTLY; THAT LAP LENGTHS, STAGGERS AND OFFSETS ARE PROVIDED; AND THAT ALL MECHANICAL CONNECTIONS ARE INSTALLED PER THE MANUFACTURER'S INSTRUCTIONS AND/OR EVALUATION REPORT. (REF. CHAPTER 20 AND SECTIONS 25.2, 25.3, & 26.6.1-26.6.3 OF ACI 318-14)
2. CAST-IN ANCHORS & EMBEDS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	COMPLY WITH SECTIONS 1.9 & 17.8.2 OF ACI 318-14.
3A. POST-INSTALLED ANCHORS (ADHESIVE)	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	ALL POST-INSTALLED ANCHORS/OWELS SHALL BE SPECIALLY INSPECTED AS REQUIRED BY THE APPROVED ICC-ES REPORT, AND SHALL COMPLY WITH SECTIONS 17.8.2, 26.7.2, AND 26.13.3.2&3 OF ACI 318-14.
3B. POST-INSTALLED ANCHORS (NON-ADHESIVE)	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	
4. USE OF REQUIRED MIX DESIGN	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT ALL MIXES USED COMPLY WITH THE APPROVED CONSTRUCTION DOCUMENTS AND CHAPTER 19 & SECTIONS 26.4.3&4 OF ACI 318-14.
5. CONCRETE SAMPLING FOR STRENGTH TESTS, SLUMP, AIR CONTENT, AND TEMPERATURE	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	COMPLY WITH SECTIONS 26.4 & 26.12 OF ACI 318-14.
6. CONCRETE & SHOTCRETE PLACEMENT	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	COMPLY WITH SECTION 26.5 OF ACI 318-14 AND SECTION 1908 OF IBC.
7. CURING TEMPERATURE AND TECHNIQUES	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT THE AMBIENT TEMPERATURE FOR CONCRETE IS KEPT AT > 50°F FOR AT LEAST 7 DAYS AFTER PLACEMENT. HIGH-EARLY-STRENGTH CONCRETE SHALL BE KEPT AT > 50°F FOR AT LEAST 3 DAYS. ACCELERATED CURING METHODS MAY BE USED. THE AMBIENT TEMPERATURE FOR SHOTCRETE SHALL BE > 40°F FOR THE SAME PERIOD OF TIME AS NOTED FOR CONCRETE. SHOTCRETE SHALL BE KEPT CONTINUOUSLY MOIST FOR AT LEAST 24 HOURS AFTER SHOTCRETING. ALL CONCRETE MATERIALS, REINFORCEMENT, FORMS, FILLERS, AND GROUND SHALL BE FREE FROM FROST. IN HOT WEATHER CONDITIONS ENSURE THAT APPROPRIATE MEASURES ARE TAKEN TO AVOID PLASTIC SHRINKAGE CRACKING AND THAT THE SPECIFIED WATER/CEMENT RATIO IS NOT EXCEEDED. (REF SECTIONS 26.5.3 THRU 26.5.5 OF ACI 318-14)
8. PRE-STRESSED CONCRETE	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	COMPLY WITH SECTION 26.10.2 OF ACI 318-14.
9. ERECTION OF PRECAST CONCRETE	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT ALL PRECAST ELEMENTS ARE LIFTED, ASSEMBLED AND BRACED IN ACCORDANCE WITH THE APPROVED CONSTRUCTION DOCUMENTS.
10. STRENGTH VERIFICATION FOR REMOVAL OF SHORES/FORMS AND FOR POST-TENSIONED CONCRETE	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT ADEQUATE STRENGTH HAS BEEN ACHIEVED PRIOR TO THE REMOVAL OF SHORES AND FORMS OR THE STRESSING OF POST-TENSIONED TENDONS.
11. FORMWORK	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT THE FORMS ARE PLACED PLUMB AND CONFORM TO THE SHAPES, LINES, AND DIMENSIONS OF THE MEMBERS AS REQUIRED BY THE APPROVED CONSTRUCTION DOCUMENTS.
12. VERIFICATION OF WELDABILITY OF REINFORCING STEEL	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY WELDABILITY OF REINFORCING STEEL BASED UPON CARBON EQUIVALENT AND IN ACCORDANCE WITH AWS D1.4 & SECTION 26.6.4.1 OF ACI 318-14.

STRUCTURAL STEEL (IBC 1705.2.1, 1705.12.1 & 1705.13.1)

PRIOR TO WELDING (TABLE N5.4-1, AISC 360-10):			
1. VERIFY WELDING PROCEDURES (WPS) AND CONSUMABLE CERTIFICATES	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	VERIFY TYPE AND GRADE OF MATERIAL.
2. MATERIAL IDENTIFICATION	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	
3. WELDER IDENTIFICATION	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	A SYSTEM SHALL BE MAINTAINED BY WHICH A WELDER WHO HAS WELDED A JOINT OR MEMBER CAN BE IDENTIFIED.
4. FIT-UP GROOVE WELDS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY JOINT PREPARATION, DIMENSIONS, CLEANLINESS, TACKING, AND BACKING.
5. ACCESS HOLES	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY CONFIGURATION AND FINISH.
6. FIT-UP OF FILLET WELDS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY ALIGNMENT, GAPS AT ROOT, CLEANLINESS OF STEEL SURFACES, AND TACK WELD QUALITY AND LOCATION.
DURING WELDING (TABLE N5.4-2, AISC 360-10):			
1. USE OF QUALIFIED WELDERS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT WELDERS ARE APPROPRIATELY QUALIFIED.
2. CONTROL AND HANDLING OF WELDING CONSUMABLES	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY PACKAGING AND EXPOSURE CONTROL.
3. CRACKED TACK WELDS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT WELDING DOES NOT OCCUR OVER CRACKED TACK WELDS.
4. ENVIRONMENTAL CONDITIONS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY WIND SPEED IS WITHIN LIMITS AS WELL AS PRECIPITATION AND TEMPERATURE.
5. WPS FOLLOWED	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY ITEMS SUCH AS SETTINGS ON WELDING EQUIPMENT, TRAVEL SPEED, WELDING MATERIALS, SHIELDING GAS TYPE/FLOW RATE, PREHEAT APPLIED, INTERPASS TEMPERATURE MAINTAINED, AND PROPER POSITION.
6. WELDING TECHNIQUES	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY INTERPASS AND FINAL CLEANING. EACH PASS IS WITHIN PROFILE LIMITATIONS, AND QUALITY OF EACH PASS.
AFTER WELDING (TABLE N5.4-3, AISC 360-10):			
1. WELDS CLEANED	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT WELDS HAVE BEEN PROPERLY CLEANED.
2. SIZE, LENGTH, AND LOCATION OF WELDS	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
3. WELDS MEET VISUAL ACCEPTANCE CRITERIA	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	VERIFY CRACK PROHIBITION, WELD/BASE METAL FUSION, CRATER CROSS SECTION, WELD PROFILES, WELD SIZE, UNDERCUT, AND POROSITY ARE ALL ACCEPTABLE.
4. ARC STRIKES	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
5. K-AREA	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
6. BACKING & WELD TABS REMOVED	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
7. REPAIR ACTIVITIES	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
8. DOCUMENT ACCEPTANCE OR REJECTION OF WELDED JOINT/MEMBER	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
NONDESTRUCTIVE TESTING (SECTION N5.5, AISC 360-10):			
1. CJP WELDS (RISK CAT. II)	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	ULTRASONIC TESTING SHALL BE PERFORMED ON 10% OF CJP GROOVE WELDS IN BUTT, T- AND CORNER JOINTS SUBJECT TO TRANSVERSELY APPLIED TENSION LOADING IN MATERIALS 5/16 INCH THICK OR GREATER. TESTING RATE MUST BE INCREASED IF > 5% OF WELDS TESTED HAVE UNACCEPTABLE DEFECTS PER SECTION N5.5F.
2. CJP WELDS (RISK CAT. III OR IV)	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	ULTRASONIC TESTING SHALL BE PERFORMED ON ALL CJP GROOVE WELDS IN BUTT, T- AND CORNER JOINTS SUBJECT TO TRANSVERSELY APPLIED TENSION LOADING IN MATERIALS 5/16 INCH THICK OR GREATER. A REDUCTION IN THE RATE OF ULTRASONIC TESTING IS ALLOWED PER SECTION N5.5E.
3. ACCESS HOLES (FLANGE > 2")	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	MAGNETIC PARTICLE TESTING OR PENETRANT TESTING SHALL BE PERFORMED. ANY CRACK SHALL BE DEEMED UNACCEPTABLE.
4. WELDED JOINTS SUBJECT TO FATIGUE	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	REFER TO APPENDIX 3, TABLE A-3.1.
PRIOR TO BOLTING (TABLE N5.6-1, AISC 360-10):			
NOT REQUIRED IF ONLY SNUG-TIGHT JOINTS ARE SPECIFIED [PER SECTION N5.6(1) OF AISC 360-10].			
1. CERTIFICATIONS OF FASTENERS	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
2. FASTENERS MARKED	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT FASTENERS HAVE BEEN MARKED IN ACCORDANCE WITH ASTM REQUIREMENTS.
3. PROPER FASTENERS FOR JOINT	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY GRADE, TYPE, AND BOLT LENGTH IF THREADS ARE EXCLUDED FROM THE SHEAR PLANE.
4. PROPER BOLTING PROCEDURE	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY PROPER PROCEDURE IS USED FOR THE JOINT DETAIL.
5. CONNECTING ELEMENTS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY APPROPRIATE FAYING SURFACE CONDITION AND HOLE PREPARATION, IF SPECIFIED, MEET REQUIREMENTS.
6. PRE-INSTALLATION VERIFICATION TESTING	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	OBSERVE AND DOCUMENT VERIFICATION TESTING BY INSTALLATION PERSONNEL FOR FASTENER ASSEMBLIES AND METHODS USED. COMPONENTS.
7. PROPER STORAGE	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY PROPER STORAGE OF BOLTS, NUTS, WASHERS, AND OTHER FASTENER COMPONENTS.
DURING BOLTING (TABLE N5.6-2, AISC 360-10):			
NOT REQUIRED IF ONLY SNUG-TIGHT JOINTS ARE SPECIFIED [PER SECTION N5.6(1) OF AISC 360-10]. NOT REQUIRED FOR PRETENSIONED JOINTS USING TURN-OFF-THE-NUT METHOD WITH MATCH-MARKING, DIRECT-TENSION-INDICATORS, OR TWIST-OFF TYPE TENSION CONTROL METHOD [PER SECTION N5.6(2) OF AISC 360-10].			
1. FASTENER ASSEMBLIES	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT FASTENER ASSEMBLIES ARE OF SUITABLE CONDITION, PLACED IN ALL HOLES, AND WASHERS ARE POSITIONED AS REQUIRED.
2. SNUG-TIGHT PRIOR TO PRETENSIONING	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT JOINTS ARE BROUGHT TO SNUG-TIGHT CONDITION PRIOR TO PRETENSIONING OPERATION.
3. FASTENER COMPONENT	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT FASTENER COMPONENT IS NOT TURNED BY WRENCH PREVENTED FROM ROTATING.
4. PRETENSIONED FASTENERS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	VERIFY THAT FASTENERS ARE PRETENSIONED IN ACCORDANCE WITH RCSC SPECIFICATION, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID POINT TOWARD THE FREE EDGES.
AFTER BOLTING (TABLE N5.6-3, AISC 360-10):			
1. DOCUMENT ACCEPTANCE OR REJECTION OF BOLTED CONNECTIONS	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	
OTHER STEEL INSPECTIONS (SECTION N5.7, AISC 360-10; TABLES J8-1 & J10-1, AISC 341-10):			
1. STRUCTURAL STEEL DETAILS	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	ALL FABRICATED STEEL OR STEEL FRAMES SHALL BE INSPECTED TO VERIFY COMPLIANCE WITH THE DETAILS SHOWN IN THE CONSTRUCTION DOCUMENTS, SUCH AS BRACES, STIFFENERS, MEMBER LOCATIONS, AND PROPER APPLICATION OF JOINT DETAILS AT EACH CONNECTION.
2. ANCHOR RODS AND OTHER EMBEDMENTS SUPPORTING STRUCTURAL STEEL	<input type="checkbox"/> CONTINUOUS	<input checked="" type="checkbox"/> PERIODIC	SHALL BE ON THE PREMISES DURING THE PLACEMENT OF ANCHOR RODS AND OTHER EMBEDMENTS SUPPORTING STRUCTURAL STEEL FOR COMPLIANCE WITH CONSTRUCTION DOCUMENTS. VERIFY THE DIAMETER, GRADE, TYPE, AND LENGTH OF THE ANCHOR ROD OR EMBEDDED ITEM, AND THE EXTENT OR DEPTH OF EMBEDMENT PRIOR TO PLACEMENT OF CONCRETE.
3. REDUCED BEAM SECTIONS (RBS)	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	VERIFY CONTOUR AND FINISH AS WELL AS DIMENSIONAL TOLERANCES (SEE TABLE J8-1 OF AISC 341-10).
4. PROTECTED ZONES	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	VERIFY THAT NO HOLES OR UNAPPROVED ATTACHMENTS ARE MADE WITHIN THE PROTECTED ZONE (SEE TABLE J8-1 OF AISC 341-10).
5. H-PILES	<input checked="" type="checkbox"/> CONTINUOUS	<input type="checkbox"/> PERIODIC	VERIFY THAT NO HOLES OR UNAPPROVED ATTACHMENTS OCCUR WITHIN THE PROTECTED ZONES OF PILING (SEE TABLE J10-1 OF AISC 341-10).




TGRWA

TyK Gustafson Reckers Wilson Andrews, LLC
Structural Engineers

600 West Van Buren Suite 900 Chicago Illinois 60607
Phone: 312.341.0055 Fax: 312.341.9995 www.tgrwa.com

CHURCH OF THE HOLY COMFORTER
SOLAR PROJECT
543 BEULAH ROAD NE
VIENNA, VA 22182



DATE: 02/27/2024
LICENSE EXPIRES: 02/28/2025

DATE: 09/07/2024

DESIGNED BY: **SEO**

NO.	DATE:	REVISIONS
09/07/2024		PRELIMINARY REVIEW
02/27/2024		PERMIT

TESTING & INSPECTION NOTES

S0.2

ABBREVIATIONS			
ADDL	ADDITIONAL	LL	LIVE LOAD
ALT	ALTERNATE	LLH	LONG LEG HORIZONTAL
ALUM	ALUMINUM	LLV	LONG LEG VERTICAL
APPROX	APPROXIMATE	LSL	LONG SLOT
ARCH	ARCHITECT(URAL)	LVL	LAMINATED VENEER LUMBER
ASSY	ASSEMBLY	LW	LIGHT WEIGHT
B/	BOTTOM OF	MAX	MAXIMUM
BLDG	BUILDING	MECH	MECHANICAL
BM	BEAM	MED	MEDIUM
BOT	BOTTOM	MEP	MECHANICAL ELECTRICAL PLUMBING
BRDG	BRIDGING	MEZZ	MEZZANINE
BRG	BEARING	MFR	MANUFACTURER
BRKT	BRACKET	MIN	MINIMUM
BW	BOTH WAYS	MISC	MISCELLANEOUS
C/C	CENTER TO CENTER	MK	MARK
CCD	CHICAGO CITY DATUM	MO	MASONRY OPENING
CIP	CAST IN PLACE	MTL	METAL
CJ	CONSTRUCTION JOINT, CONTROL JOINT	NIC	NOT IN CONTRACT
CJP	COMPLETE JOINT PENETRATION	NOM	NOMINAL
CL	CENTERLINE	NS	NEAR SIDE
CLR	CLEAR	NTS	NOT TO SCALE
CMU	CONCRETE MASONRY UNIT	NW	NORMAL WEIGHT
COL	COLUMN	OC	ON CENTER
CONC	CONCRETE	OD	OUTSIDE DIAMETER
CONN	CONNECTION	OPNG	OPENING
CONT	CONTINUOUS	OPP	OPPOSITE
COORD	COORDINATE, COORDINATION	OPP HD	OPPOSITE HAND
CTR	CENTER	PC	PRECAST CONCRETE
CU FT	CUBIC FOOT	PCF	POUNDS PER CUBIC FOOT
CU YD	CUBIC YARD	PERIM	PERIMETER
DBA	DEFORMED BAR ANCHOR	PERP	PERPENDICULAR
DEG	DEGREE	PL	PLATE
DEMO	DEMOLISH	PLF	POUNDS PER LINEAR FOOT
DIA	DIAMETER	PLUMB	PLUMBING
DIM	DIMENSION	PLYWD	PLYWOOD
DL	DEAD LOAD	PROJ	PROJECT
DWG	DRAWING	PSF	POUNDS PER SQUARE FOOT
DWGS	DRAWINGS	PSI	POUNDS PER SQUARE INCH
(E)	EXISTING	PSL	PARALLEL STRAND LUMBER
EA	EACH	PT	POST TENSIONED
EF	EACH FACE	QTY	QUANTITY
EL	ELEVATION	RAD	RADIUS
ELEC	ELECTRICAL	REBAR	REINFORCING BAR
EMBED	EMBEDDED	REF	REFER, REFERENCE
ENGR	ENGINEER	REINF	REINFORCE, REINFORCEMENT
EOD	EDGE OF DECK	REQD	REQUIRED
EOS	EDGE OF SLAB	REV	REVISION
EQ	EQUAL, EQUIVALENT	RO	ROUGH OPENING
EQUIP	EQUIPMENT	SC	SLIP CRITICAL
EW	EACH WAY	SCHED	SCHEDULE
EXIST	EXISTING	SE	STRUCTURAL ENGINEER
EXP JT	EXPANSION JOINT	SECT	SECTION
EXT	EXTERIOR	SF	SQUARE FOOT
FF	FINISHED FLOOR	SHT	SHEET
FIN	FINISH	SIM	SIMILAR
FLR	FLOOR	SOG	SLAB ON GRADE
FDN	FOUNDATION	SPECS	SPECIFICATIONS
FS	FAR SIDE	SQ	SQUARE
FT	FOOT, FEET	SQ FT	SQUARE FOOT (FEET)
FTG	FOOTING	SS	STAINLESS STEEL
GA	GAUGE	SSL	SHORT SLOT
GALV	GALVANIZED	STD	STANDARD
GB	GRADE BEAM	STIFF	STIFFENER
GC	GENERAL CONTRACTOR	STL	STEEL
GYP	GYPSPUM	STRUCT	STRUCTURAL
GYP BD	GYPSPUM BOARD	SYM	SYMMETRICAL
HORIZ	HORIZONTAL	t	THICKNESS
ID	INSIDE DIAMETER	T&B	TOP & BOTTOM
IN	INCH(ES)	T/	TOP OF
INFO	INFORMATION	TEMP	TEMPORARY
INSUL	INSULATION	THRU	THROUGH
INT	INTERIOR	TYP	TYPICAL
JST	JOIST	UNO	UNLESS NOTED OTHERWISE
JT	JOINT	VERT	VERTICAL
K	KIPS	VIF	VERIFY IN FIELD
KSI	KIPS PER SQUARE INCH	W/	WITH
LAT	LATERAL	W/O	WITHOUT
LB	POUND	WF	WIDE FLANGE
LFH	LONG FACE HORIZONTAL	WP	WORKING POINT
LFV	LONG FACE VERTICAL	WWF	WELDED WIRE FABRIC
LIN	LINEAR	YD	YARD

MARK DESIGNATIONS	
Bx	INDICATES BEAM TYPE. REFER TO BEAM SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
BPx	INDICATES BASE PLATE TYPE. REFER TO BASE PLATE SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
BFx	INDICATES BRACED FRAME TYPE. REFER TO BRACED FRAME ELEVATIONS AND DETAILS FOR ADDITIONAL INFORMATION.
Cx	INDICATES COLUMN TYPE. REFER TO COLUMN SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
CCx	INDICATES CAISSON CAP TYPE. REFER TO CAISSON CAP SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
CSx	INDICATES CAISSON TYPE. REFER TO CAISSON SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
DPx	INDICATES DRIVEN / DRILLED PILE TYPE. REFER TO DRIVEN / DRILLED PILE SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
Fx	INDICATES SPREAD FOOTING TYPE. REFER TO FOOTING SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
GBx	INDICATES GRADE BEAM TYPE. REFER TO GRADE BEAM SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
Jx	INDICATES JOIST TYPE. REFER TO JOIST SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
Lx	INDICATES LINTEL TYPE. REFER TO LINTEL SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
Px	INDICATES PIER TYPE. REFER TO PIER DETAILS FOR ADDITIONAL INFORMATION.
PCx	INDICATES PILE CAP TYPE. REFER TO PILE CAP DETAILS FOR ADDITIONAL INFORMATION.
PCBx	INDICATES PRECAST BEAM BY PRECAST MANUFACTURER.
PCPx	INDICATES PRECAST PLANK TYPE BY PRECAST MANUFACTURER.
PTBx	INDICATES POST TENSIONED BEAM TYPE. REFER TO POST TENSIONED BEAM SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.
SWx	INDICATES SHEAR WALL TYPE. REFER TO SHEAR WALL ELEVATIONS, SCHEDULES AND DETAILS FOR ADDITIONAL INFORMATION.
SWBx	INDICATES SHEAR WALL BEAM TYPE. REFER TO SHEAR WALL BEAM SCHEDULE AND DETAILS FOR ADDITIONAL INFORMATION.

HATCH PATTERNS	
	EARTH / NATIVE SOIL
	GRAVEL
	GROUT / SAND
	CONCRETE
	STEEL
	WOOD
	CONCRETE MASONRY (PLAN)
	CONCRETE MASONRY (ELEVATION)
	GEOFOAM
	PRECAST
	DEMOLITION

GENERAL SYMBOLS	
	REVISION
	REVISION CLOUD
	NORTH ARROW
	ELEVATION TARGET
	SLAB STEP
	RAMP SLOPE UP
	RAMP SLOPE DOWN
	INDICATES SPAN DIRECTION OF ONE WAY SLAB OR METAL ROOF DECK
	INDICATES SPAN DIRECTION OF TWO WAY SLAB
TYPICAL STEEL BEAM DESIGNATIONS	
	INDICATES NUMBER OF X/X" @X" WELDED HEADED STUDS UNIFORMLY SPACED ALONG THE BEAM AND SLAB INTERFACE LENGTH. REFER TO DETAIL XX/SX.X FOR ADDITIONAL INFORMATION.
	INDICATES REQUIRED CAMBER UP FOR FLOOR FRAMING. INSTALL ALL BEAMS AND GIRDERS WITHOUT CAMBER SPECIFIED WITH NATURAL CAMBER UP.
	INDICATES ELEVATION DIFFERENCE BETWEEN TYPICAL 1/STEEL ELEVATION AND THIS MEMBER
STEEL FRAMING SYMBOLS	
	MOMENT CONNECTION
	DRAG STRUT CONNECTION
	SLIP CRITICAL CONNECTION
	SLIDE BEARING CONNECTION
	BEAM OPENING. REFER TO BEAM OPENING SCHEDULE FOR ADDITIONAL INFORMATION.
	STAIR CONNECTION
	COLUMN OR BEAM SPLICE
	COLUMN ABOVE
	ROOF DAVIT
	ROOF TIEBACK
	ROOF FALL ARREST
	ROOFTOP UNIT DESIGNATION




TGRWA

TJK Gustafson Reckers Wilson Andrews, LLC
Structural Engineers

600 West Van Buren Suite 900 Chicago, Illinois 60607
Phone: 312.341.0055 Fax: 312.341.9995 www.tgrwa.com

CHURCH OF THE HOLY COMFORTER
SOLAR PROJECT
 543 BEULAH ROAD NE
 VIENNA, VA 22182



DATE: 02/27/2024
LICENSE EXPIRES: 02/28/2025


DATE: 09/07/2024

DESIGNED BY: SEO


NO.	DATE:	REVISIONS
09/07/2024		PRELIMINARY REVIEW
02/27/2024		PERMIT

SYMBOLS & ABBREVIATION

S0.3



1 CANOPY FOUNDATION PLAN



SCALE: 1/8" = 1'-0"

NOTES:


- RECORDS OF ANY EXISTING SUBGRADE INTERFERENCES OTHER THAN THOSE INTERFERENCES SHOWN OR INDICATED ON THE CONSTRUCTION DOCUMENTS, ARE NOT CURRENTLY AVAILABLE. DURING EXCAVATION WORK, INTERFERENCES MAY BE DISCOVERED. CONTRACTOR SHALL DOCUMENT CONSTRUCTION-RELATED DIMENSIONS OF ALL INTERFERENCES. CONTRACTOR TO FURNISH THE ABOVE INFORMATION IN THE FORM OF DETAILED SKETCHES TO THE STRUCTURAL ENGINEER FOR REVIEW.
- GENERAL CONTRACTOR SHALL COORDINATE WITH CIVIL/SITE LAYOUT FOR LOCATION OF CANOPY STRUCTURE. COORDINATE WITH THE PARKING LAYOUT SUCH THAT THE NEW CANOPY COLUMNS DO NOT INTERFERE WITH ANY PARKING SPACES.



TGRWA

Tyik Gustafson Reders Wilson Andrews, LLC
Structural Engineers
600 West Van Buren Suite 900 Chicago, Illinois 60607
Phone: 312.341.0055 Fax: 312.341.9996 www.tgrwa.com

CHURCH OF THE HOLY COMFORTER
SOLAR PROJECT
543 BEULAH ROAD NE
VIENNA, VA 22182



DATE: 02/27/2024
LICENSE EXPIRES: 02/28/2025


DATE: 09/07/2024

DESIGNED BY: SEO

NO.	DATE	REVISIONS
08/07/2024		PRELIMINARY REVIEW
02/27/2024		PERMIT

CANOPY
FOUNDATION
PLAN

S1.1



1 CANOPY FRAMING PLAN

0 2' 4' 8' 16'


SCALE: 1/8" = 1'-0"



TGRWA

Tyik Gustafson Reders Wilson Andrews, LLC
Structural Engineers
600 West Van Buren Suite 900 Chicago, Illinois 60607
Phone: 312.341.0055 Fax: 312.341.9595 www.tgrwa.com

CHURCH OF THE HOLY COMFORTER
SOLAR PROJECT
543 BEULAH ROAD NE
VIENNA, VA 22182



DATE: 02/27/2024
LICENSE EXPIRES: 02/28/2025


DATE: 09/07/2024

DESIGNED BY: SEO

NO.	DATE	REVISIONS
08/07/2024		PRELIMINARY REVIEW
02/27/2024		PERMIT

CANOPY FRAMING PLAN


S1.2



13'-0" MIN CLEAR TO LOW POINT OF BEAM

T/PIER
 EL = SEE PLAN
 T/GRADE
 EL = SEE CIVIL DWGS

1 CANOPY FRAMING SECTION




- NOTES:
1. WP - INDICATES WORK POINT INTERSECTION OF STRUCTURAL MEMBER CENTERLINES.
 2. CANOPY FRAMING IS SYMMETRIC ABOUT THE COLUMN CENTERLINE.



TGRWA

Tyik Gustafson Reders Wilson Andrews, LLC
 Structural Engineers
 600 West Van Buren Suite 900 Chicago, Illinois 60607
 Phone: 312.341.0055 Fax: 312.341.9596 www.tgrwa.com

CHURCH OF THE HOLY COMFORTER
 SOLAR PROJECT
 543 BEULAH ROAD NE
 VIENNA, VA 22182



DATE: 02/27/2024
 LICENSE EXPIRES: 02/28/2025


DATE: 09/07/2024

DESIGNED BY: SEO

NO.	DATE	REVISIONS
08/07/2024		PRELIMINARY REVIEW
02/27/2024		PERMIT


FRAMING SECTION

S2.1




1 BASE PLATE AND CONCRETE PIER AND FOOTING SECTION
SCALE: NOT TO SCALE

NOTES:
1. REFER TO FOUNDATIONS NOTES ON S0.1.
2. ALL REINFORCEMENT SHALL BE EPOXY COATED.




2 BASE PLATE AND CONCRETE DRILLED PIER PLAN
SCALE: NOT TO SCALE


NOTES:
1. PLACE (1) #7 VERTICAL W/ TOP HOOK WITHIN 4" OF EACH ANCHOR.




3 TYPICAL TOP BEAM TO COLUMN CONNECTION DETAIL
SCALE: NOT TO SCALE



4 TYPICAL PURLIN TO BEAM CONNECTION
SCALE: NOT TO SCALE




5 TYPICAL PURLIN TO BEAM CONNECTION
SCALE: NOT TO SCALE



6 TYPICAL PURLIN BLOCKING CONNECTION DETAIL
SCALE: NOT TO SCALE

NOTES:
1. CFS - INDICATES COLD-FORMED STEEL. SEE NOTES ON S0.1.




7 TYPICAL SPLICE PLATE CONNECTION DETAIL
SCALE: NOT TO SCALE



TGRWA

Tyik Gustafson Reckers Wilson Andrews, LLC
Structural Engineers
600 West Van Buren Suite 900 Chicago, Illinois 60607
Phone: 312.341.0055 Fax: 312.341.9995 www.tgrwa.com

CHURCH OF THE HOLY COMFORTER
SOLAR PROJECT
543 BEULAH ROAD NE
VIENNA, VA 22182



DATE: 09/07/2024

DESIGNED BY: SEO

NO.	DATE	REVISIONS
09/07/2024		PRELIMINARY REVIEW
02/27/2024		PERMIT

DETAILS

S3.1