

A&M CONCRETE CORPORATION**Lullaby Ln SW from Tapawingo to Harmony and Harmony Dr SW from Lullaby to End****IFB 24-12 ON-CALL ROADWAY MAINTENANCE**

| ITEM NO. | DESCRIPTION | ESTIMATE QUANTITY | UNIT | UNIT PRICE | AMOUNT |
|----------|---|-------------------|------|------------|-------------|
| | | | | | |
| 1 | REMOVE SHRUBS | 31 | EA | \$165.00 | \$5,115.00 |
| 2 | REMOVE TREES (2" – 6" DIA.) | 4 | EA | \$825.00 | \$3,300.00 |
| 3 | REMOVE TREES (OVER 6" – 18" DIA.) | 2 | EA | \$1,250.00 | \$2,500.00 |
| 4 | GRIND TREE STUMP BELOW GRADE (18" DIA. AND SMALLER) | 6 | EA | \$435.00 | \$2,610.00 |
| 5 | REMOVE AND DISPOSE OF CONCRETE DRIVEWAY APRON | 100 | SY | \$20.00 | \$2,000.00 |
| 6 | REMOVE AND DISPOSE OF CONCRETE SIDEWALK | 103 | SY | \$8.00 | \$824.00 |
| 7 | REMOVE AND DISPOSE OF CONCRETE CURB AND/OR CURB AND GUTTER | 250 | LF | \$8.00 | \$2,000.00 |
| 8 | REMOVE AND DISPOSE OF PAVEMENT (OVER 4" DEPTH) | 85 | SY | \$16.00 | \$1,360.00 |
| 9 | INSTALL SIGN INCLUDING PROVIDING AND INSTALLING NEW 2" SQUARE BREAKAWAY POST | 2 | EA | \$525.00 | \$1,050.00 |
| 10 | SAWCUT ASPHALT PAVEMENT (1" – 4" DEPTH) | 250 | LF | \$2.00 | \$500.00 |
| 11 | SAWCUT CONCRETE CURB AND GUTTER, AND DRIVEWAY ENTRANCES | 35 | LF | \$3.00 | \$105.00 |
| 12 | REGULAR EXCAVATION – REMOVE AND DISPOSE | 150 | CY | \$58.00 | \$8,700.00 |
| 13 | VDOT 21-A STONE OR 21-B STONE (COMPACTED IN PLACE PER VDOT STANDARDS AND SPECIFICATIONS) | 135 | TON | \$45.00 | \$6,075.00 |
| 14 | CONCRETE CURB OR CURB AND GUTTER (PER VIENNA STANDARD R-2, OR VDOT CG-2, CG-3, CG-6, OR CG-7) | 250 | LF | \$34.00 | \$8,500.00 |
| 15 | CONCRETE DRIVEWAY ENTRANCE, 6" THICK CONCRETE -ARL STD R-2.4C (includes 21A) | 95 | SY | \$140.00 | \$13,300.00 |
| 16 | 4" THICKNESS CONCRETE SIDEWALK | 440 | SY | \$66.00 | \$29,040.00 |
| 17 | DETECTABLE WARNING SURFACE | 40 | SF | \$58.00 | \$2,320.00 |
| 18 | ASPHALT TYPE BM-25, A THRU D | 21 | TON | \$170.00 | \$3,570.00 |

IFB 24-12 ON-CALL ROADWAY MAINTENANCE

| | | | | | |
|----|---|-----|-----|------------------|---------------------|
| 19 | ASPHALT TYPE SM-9.5, A THRU D | 10 | TON | \$190.00 | \$1,900.00 |
| 20 | ASPHALT PAVEMENT MILLING (UP TO 2") | 150 | SY | \$14.00 | \$2,100.00 |
| 21 | REMOVE EXISTING INLET STRUCTURE | 1 | EA | \$2,100.00 | \$2,100.00 |
| 22 | FURNISH AND INSTALL CURB DROP INLET, VDOT DI-3B, OR DI-3C WITH L = 12' (DEPTH 5' OR LESS) | 2 | EA | \$7,900.00 | \$15,800.00 |
| 23 | FURNISH AND INSTALL 4' DIAMETER MANHOLE (DEPTH 5' OR LESS) | 2 | EA | \$5,800.00 | \$11,600.00 |
| 24 | FURNISH AND INSTALL CL-III RCP, 18" DIAMETER | 55 | LF | \$140.00 | \$7,700.00 |
| 25 | ADJUST STORM OR SANITARY MANHOLE FRAME AND COVER (1" – 6") | 1 | EA | \$975.00 | \$975.00 |
| 26 | REMOVE AND REPLACE REINFORCED CONCRETE INLET TOP (INCLUDES REMOVAL OF EXISTING FRAME AND COVER, AND RE-USE OF THE EXISTING FRAME AND COVER) | 5 | SY | \$340.00 | \$1,700.00 |
| 27 | FURNISH AND INSTALL POP-UP DRAINAGE EMITTER AS DESCRIBED IN SECTION "F" OF THIS SPECIFICATION HEREIN. | 1 | EA | \$350.00 | \$350.00 |
| 28 | ADJUST WATER METER BOXES (VERTICAL ADJUSTMENT ONLY) | 6 | EA | \$475.00 | \$2,850.00 |
| 29 | REMOVE AND RELOCATE MAILBOX | 1 | EA | \$395.00 | \$395.00 |
| 30 | SODDING (TO INCLUDE 2" TOPSOIL AND FERTILIZATION) | 390 | SY | \$10.00 | \$3,900.00 |
| | | | | TOTAL BID | \$144,239.00 |