

NB+C Engineering Services

Penthouse Floor Structural Analysis

Prepared for T-Mobile: Anchor

SITEINFORMATION

Address	301 Maple Ave West
	Vienna, VA 22180
	Lat: 38.89820100°
	Long: -77.27086100°
T-Mobile Site Number	7WAC050A
T-Mobile Site Name	White Oak Tower
NB+C Project Number	100595
Date	May 5, 2021

TABLE OF CONTENTS

1.0 INTRODUCTION	3
2.0 EQUIPMENT LOADING	3
Table 1 – Proposed Equipment Information	3
Table 2 – Existing Equipment Information	3
3.0 ASSUMPTIONS	3
4.0 APPLICABLE CODES AND STANDARDS	4
5.0 ANALYSIS	4
6.0 CONCLUSIONS & RECOMMENDATIONS	4
APPENDIX A: PLAN AND ELEVATION	6
APPENDIX B: CALCULATIONS	7

1.0 INTRODUCTION

The existing structure is a 81'-6" ± building located in Vienna, VA.

T-Mobile has proposed to reconfigure the site and install the new equipment as shown in the tables below. A structural analysis was performed to see if the new loads are safely supported by the proposed antenna mounts and to verify if the existing structure is in compliance with the applicable codes and standards. Information we have received and used for this analysis includes:

- RFDS provided by T-Mobile dated February 26, 2021
- Preliminary Construction Drawings prepared by NB+C, dated April 19, 2021
- Previous Construction Drawings by NB+C, dated June 10, 2020
- Previous Construction Drawings by Advantage Engineers, dated September 3, 2010
- Previous Structural Assessment by Adams-Mirza Engineering, dated October 31, 2007
- Construction Drawings prepared by Support Engineering, dated September 03, 2014
- Site Audit Photos dated February 10, 2021

2.0 EQUIPMENT LOADING

As per the information provided to us, the following tables show the proposed and existing equipment installation by T-Mobile.

Mounting Level (ft)	Center Line Elevation (ft)	Number	Manufacturer	Equipment Model	Carrier	Feed Line Size (in)	Note
Existing Penthouse		1	-	6160 (63"x25.6"x33.5", 1500lbs)	TMahila	-	-
		1	-	B160 (63"x26.0"x26.0", 2000lbs)			
		1	-	6'x6' Fiberglass Grating Skid	-	-	-

Table 1 – Proposed Equipment Information

Table 2 – Existing Equipment Information

Mounting Level (ft)	Center Line Elevation (ft)	Number	Manufacturer	Equipment Model	Carrier	Feed Line Size (in)	Note
Existing F	Penthouse	1	-	6102	T-Mobile	-	1

Note: 1. Existing equipment to remain. 2. Existing equipment to be removed, was not considered in this analysis.

3.0 ASSUMPTIONS

This report is based on the theoretical capacity of the existing/proposed structural elements and is not an assessment of the overall suitability of the existing Structure or its components for any particular use other than specified here in this report:

• This report makes no warranties, expressed and/or implied, and disclaims any liability arising from material, fabrication and erection of the existing Structure

and any other existing or proposed components or appurtenances.

- All proposed and existing antennas, mounts, coaxial cables and appurtenances are assumed to be properly installed and configured according to manufacturer requirements.
- All existing structural elements are assumed to be in place and in good condition and were previously designed and constructed in accordance with applicable codes and standards.
- Contractor to verify existing site condition including the existing structure prior to fabrication and construction. In the event the existing structure conditions are different than the assumptions made in this report, this has to be brought to the structural engineer's attention before proceeding any further with bidding, fabrication and/or erection.

4.0 APPLICABLE CODES AND STANDARDS

The existing structure was analyzed/designed per the provisions of following applicable codes and standards:

- 2015 Virginia Uniform Statewide Building Code
- ANSI/TIA-222-G Structural Standards for Antenna Supporting Structures and Antennas
- Minimum Design Loads for Buildings and Other Structures ASCE/SEI 7-10
- AISC Manual of Steel Construction, 14th Edition ANSI/AISC 360-10

5.0 ANALYSIS

Design Loads:

- Ultimate wind speed: 115 mph
- Occupancy Category: II
- Exposure: B

Load Combinations:

- D
- D + L
- D + 0.6W
- 0.6D + 0.6W

6.0 CONCLUSIONS & RECOMMENDATIONS

As discussed above in this report, the proposed cabinets are to be installed inside the existing penthouse on a new 6'-0" x 6'-0" Fiberglass grating "skid" resting directly on the penthouse floor. Refer to construction drawings prepared by NB+C ES for the proposed location of the appurtenances, and the supporting mounts.

Based on the performed analysis of this structure for applied gravity and lateral loads, the existing structure was determined to have <u>adequate</u> capacity to support the proposed T-Mobile appurtenances.

The results in Appendix B of the report show that the additional forces imparted to the existing building

T-Mobile – 7WAC050A Penthouse Floor Structural Analysis NB+C ES Project Number 100595

May 5, 2021 Page 5 of 7

structure due to proposed appurtenance placement are within acceptable limits considering the overall configuration of the existing support structure, therefore the proposed installation may proceed as intended.

The conclusions reached by NB+C ES in this report are only applicable for the previously mentioned existing structural members supporting the T-Mobile equipment. Further, no structural gualification is made or implied by this report for existing structural members not supporting the T-Mobile equipment.

NB+C ENGINEERING SERVICES, LLC

Prepared by: Yaw O. Bonsu, E.I.T.

Respectfully Submitted by:

Krupakaran Kolandaivelu, P.E. Director of Engineering VA PE License # 49792



5/5/2021

May 5, 2021 Page **6** of **7**

APPENDIX A: PLAN AND ELEVATION









TOR	
A-2)	

	TOP OF UPPER PENTHOUSE ELEV.=81'-6"± AGL PROPOSED T-MOBILE ANTENNAS (BETA SECTOR) ELEV.=79'-0"± AGL EXISTING T-MOBILE ANTENNAS
EXISTING SPRINT EQUIPMENT CABINET (TYP)	(BETA SECTOR) ELEV.=79'-0"± AGL PROPOSED T-MOBILE ANTENNAS ELEV.=74'-0"± AGL EXISTING T-MOBILE ANTENNAS ELEV.=74'-0"± AGL
WEST	GRAPHIC SCALE







May 5, 2021 Page **7** of **7**

APPENDIX B: CALCULATIONS

PURPOSE / ASSUMPTIONS

The purpose of these calculation is to structurally qualify the poenthouse floor for supporting the T-Mobile equipment.

Proposed Cabinet Installation on Grating Skid Check:

Proposed 6160 + Proposed B160.

Wplat

W1 := 1500lbf 6160.

W2 := 2000lbf

Ws := 500lbf

Fiberglass Grating (Estimated)

B160

P2 :=
$$\frac{W1}{(26in \cdot 33.5in)} = 247.99 \cdot psf$$

P3 :=
$$\frac{W2}{(26in \cdot 33.5in)} = 330.65 \cdot psf$$

Penthouse Floor Live Load => 125 psf. Cabinets cannot rest directly on penthouse floor. Cabinets to be installed on a proposed 6' x 6' Fiberglass Grating "skid" to distribue proposed cabinet weights more evenly.

Fiber :=
$$\frac{W1 + W2 + Ws}{(72in \cdot 72in)} = 111.11 \cdot psf$$

Fiber < 125psf

Proposed "skid" installation is acceptable.