TREK
BIKES · SERVICE · GEAR

20'-11 7/8" (251 7/8")

①

5 3/4"
30"
15 5/8"
12 1/8"

3'-11 1/4" (47 1/4")   2 7/8"   5'-11 5/8" (71 5/8")   2 7/8"   3'-11 3/8" (47 3/8")

16'-8 3/4" (200 3/4")

SCALE: 3/8"=1'-0"

LED TEMPERATURE NOT TO EXCEED 3500K MAX ALLOWABLE LUMENS IS 150

002   **TRE-CL-30-RED-BSG-CLR-12-NI**

MANUFACTURE AND INSTALL ONE (1) LED FACE LIT CHANNEL LETTER
W/ NON ILLUMINATED SUB-COPY LETTERSET
FACES: .177" RED ACRYLIC FACES
TRIMCAP: 1" JEWLITE BLACK TRIM CAP
RETURNS: .063" ALUMINUM RETURN PAINTED MATTHEWS SATIN BLACK
BACKS: .063" ALUMINUM ELEMENT BACK WITH PRE-FINISHED WHITE INTERIOR
ILLUMINATION: RED LEDS
LED TEMPERATURE NOT TO EXCEED 3500K MAX ALLOWABLE LUMEN IS 150
SUBCOPY:
FACES: .125" ALUMINUM FACE PAINTED MATTHEWS SATIN BLACK
RETURNS: 2" X .063" ALUMINUM RETURN PAINTED MATTHEWS SATIN BLACK
BACKS: .063" ALUMINUM BACK
STAND OFFS: PEG LETTERS OFF FASCIA W/ 1" SPACERS. PAINT SPACERS
TO MATCH WALL COLOR SW 7015 REPOSE GRAY

.063" ALUMINUM RETURN
1" BLACK JEWELITE TRIM
.177" THK RED ACRYLIC FACE
RED LEDS
.063" ALUMINUM BACK
WEEP HOLES W/ LIGHT COVER
1" STANDOFF
COUNTER-SUNK SCREW
.125" ALUM FACE
.063" ALUM BACK
1" LONG SPACERS
WALL MATERIAL: STUCCO

3"
LED POWER SUPPLY
#10 HEX HEAD SCREWS INTO POLYETHYLENE WALL ANCHORS (TYP.)
2"
3" LONG LAG BOLTS (MIN OF 4 PER LETTER)

① **SECTION DETAIL**
SCALE: 1 ½" = 1'-0"

±50'-9"

±12'-0 ½"

±29"

±28" S

EXISTING CONDITIONS
SCALE: 3/16"=1'-0"

±50'-9"

20'-11 7/8" (251 7/8")

002

±12'-0 ½"

30"

12 1/8"

PROPOSED SIGNAGE
SCALE: 3/16"=1'-0"

NOTE: AL PREVIOUS HOLES SEALED WATER TIGHT; WALL TO BE RESTORED TO LIKE NEW
CONDITIONS AND ENTIRE ELEVATION TO BE PAINTED PANTONE 427C (GREY)

Signtech
4444 Federal Blvd San Diego, CA 92102
(619) 527-6100 signtech.com

TREK
224 Maple Ave East
Vienna, VA 22180 USA
This design is the exclusive property of Signtech and cannot be reproduced in whole or in part, without their prior written approval

Sales: Christine M. Mello
Coordinator: Brian Benson
Design: Michelle Arriaga
Engineering:

date: 02/09/22
drawing: 22-00230 **rev:** R3: 07/27/22
quote:
project: TREK_224_1

5